


# Versatile™ 4C Mailbox, 4C13D-12



COMPARTMENT CHART

| DESCRIPTION   | COMPARTMENT | COMPARTMENT SIZE          | QTY. |
|---------------|-------------|---------------------------|------|
| MAILBOX       | MB1         | 3" H x 12" W x 15" D      | 12   |
| OUTGOING MAIL | OM2         | 6-1/2" H x 12" W x 15" D  | 1    |
| PARCEL        | PL6         | 20-1/2" H x 12" W x 15" D | 2    |

PRODUCT SERIES: VERSATILE™ 4C FRONT LOAD MAILBOX



|                |            |               |   |
|----------------|------------|---------------|---|
| MODEL          | 4C13D-12   | REV           | A |
| SCALE          | NONE       | LAST REV DATE |   |
| DRAWING NUMBER | 4C13D-12CS | DRAWN BY      |   |

- Notes:
- This module meets the USPS STD-4C requirements for installation defined below when the mailbox is installed per the dimensions provided on this drawing.
    - At least one customer compartment shall be positioned less than 48" above finished floor (AFF).
    - No parcel locker (interior bottom shelf) shall be positioned less than 15" AFF.
    - No patron (tenant) lock shall be positioned more than 67" AFF.
    - No customer compartment (interior bottom shelf) shall be positioned less than 28" AFF.
    - The USPS Arrow lock shall be positioned 36"-48" AFF.
  - This 4C mailbox can also be used for private applications.
  - The rough opening width for multi-unit 4C installations = (the sum of all actual unit widths) - 1 1/8".